KADUR DIVISION.

Dated 2nd September 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 20th September 1913, for constructing Students' Home at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A. M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Students' Home at Chikmagalur"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing Students' Home at Chikmagalur.

No.	Items of work	Per	Quantity
1	Earthwork excavation of filling in basement ...	C. yd.	102
2	Concrete	C. ft.	677
3	Burnt stone in mortar	"	2,434
4	Burnt brick in mortar	"	2,995
5	Chunam plastering	Sq.	61·93
6	White and colourwashing	"	61·93
7	Burnt stone slabs...	S. ft.	702
8	Teakwood work, wrought and put up	C. ft.	117·20
9	Roofing with 1st class Mangalore tiles on teak reepers including chunam borders.	Sq.	29·42
10	Ridge tiles set in mortar	R. ft.	107
11	Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointing.	Sq.	9·60
12	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	"	4·83
13	Teakwood doors, panelled, with iron works, etc., complete. ...	S. ft.	117
14	Teakwood windows inside glazed and outside panelled shutters, etc., complete.	"	297
15	Teakwood shelves $1\frac{1}{2}$' panelled and $\frac{1}{2}$ glazed with iron works, etc., complete.	"	162
16	Wood oiling 2 coats for doors and windows ...	Sq.	16·42
17	Chacolate painting	"	7·11
18	Cement pointing	"	4·90
19	Teakwood eave board, plain	R. ft.	268
20	Burnt stone slab pillar	S. ft.	162
21	Clearing site and levelling road	Lump sum	

K. PONNAPPA,
Executive Engineer.